Sl. No.	Description of Work	Unit	Quantity
5	Cement concrete bond, bearing and cornice slabs including lead, lift, necessary moulds for laying concrete and half an inch thick cement plastering of all exposed portions (proportion of concrete 1 cement; 3 sand; 6 stone jelly to be screened through a screen of $\frac{3}{4}$ inch meshes)	100 C.ft.	1,200 C.ft.
6	Chunam pointing	100 S.ft.	25,000 S.ft.
7	Chunam plastering stone masonry walls	100 ,,	1,000 ,,
8	Supplying and erecting doors for big door ways consisting of Angle Iron frames and G. I. Sheet shutters including hinges, locking arrangements both from outside and inside as per approved design	Sq. foot	1,690 S.ft.
9	Supplying and fixing Teakwood door frames including one coat of Silicate painting	,,	360 ,,
10	Supplying and fixing Teakwood window frames with one inch diameter round iron bars including one coat of Silicate painting	,,	960 ,,
11	Supplying and fixing Teakwood ventilator frames with one inch diameter round iron bars including one coat of Silicate painting	,,	400 S.ft.
12	Flooring with burnt stone slabs, 4 inches thick, two lines dressed over 6" thick concrete (broken stone in sand mortar) bed including cement pointing	100 ,,	5,000 ,,
13	Supplying Teakwood scantlings		520 C.ft.

R. N. MIRZA,
Senior Executive Engineer.

HASSAN DIVISION—(MYSORE RAILWAYS).

Abstract Notification dated 27—28th July 1935.

The attention of the public is invited to the detailed Notification, dated 18th July 1935, published in the *Mysore Gazette*, dated 25th July 1935, on pages 1466-1467 of Part VI, *re*: collecting and spreading broken stone ballast on Mysore-Arsikere Railway. The last date for receipt of tender is 19th August 1935 up to 12 NOON.

Abstract Notification dated 2nd August 1935.

The attention of the public is invited to the detailed Notification, dated 24th July 1935, published in the *Mysore Gazette*, dated 1st August 1935, on pages 1509-1510 of Part VI, regarding removing projections and overhangings in slopes of cuttings on Mysore-Arsikere Railway.

The last date for receipt of tender is 23rd August 1935.

Notification dated 2nd August 1935.

Notice is hereby given that the sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, on any working day up to 3 P.M., on Monday 26th August 1935, for constructing Station Building at Krishnarajasagara Flag Station on Mysore-Arsikere Railway.

1. An approximate estimate of quantities is given in the following schedule. The quantities are not guaranteed. The work should be completed by the end of April 1936; showing monthly progress as noted in the tender.

2. Detailed estimates and plans, etc., and conditions of schedule agreement, may be seen at the Executive Engineer's Office, Mysore Railways, Hassan, on all working days, between 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, on payment of one rupee.

4. Every tender must be accompanied by a deposit of Rs. 100 (one hundred) in cash as earnest money and should be superscribed "Tenders for constructing Station Building at Krishnarajasagara Flag Station on Mysore-Arsikere Railway," in default of which, tenders will be rejected.

5. The earnest money of rejected tenders will be returned as early as possible after the tenders are disposed of and in the case of accepted tender, it would be held as a part of security under clause 4 of the Schedule Agreement referred to.

6. The final acceptance of any tender will rest with the Superintendent, Way and Works, Mysore Railways, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

7. The name of the contractor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful tenderer is required to execute the usual schedule agreement, in default of which, his tender will be considered as cancelled and the earnest money is forfeited to Government.

9. Definite rates against each item of work in the Schedule should be noted both in figures and in words.

10. In case the accepted tenderer quarries stone, earth, kankar, sand, etc., from Railway, Government, or Forest land for use on this work, royalty at the rates fixed by the Government will be recovered from his bills.

11. The whole of the work specified in the agreement to be completed as specified in para 1 above, failing which or failing to carry out any of the conditions of the agreement, the whole of the money held in deposit or so much of it as the Agent considers proper will, without prejudice to any other legal or equitable right or remedy which the Agent may have, be absolutely forfeited to the Agent.

12. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any items of work or specification, the decision of the Superintendent, Way and Works, shall be final.

Schedule.

Sl. No.	Items of work	Unit	Quantity	Rate	Cost
				Rs. a. p.	Rs. a. p.
1	Earthwork excavating founds and filling in basement with spoil	1,000 C.ft.	3,000		
2	Concrete broken stone in sand mortar as per specification	100 ,,	1,500		
3	Size stone in sand mortar foundation as per specification	,,	1,500		
4	Burnt brick in mortar in superstructure ..	,,	3,000		
5	Size stone in mortar in superstructure including corner dressing, etc., as per specification	,,	3,000		
6	Burnt brick in arch work including all charges	,,	200		
7	Burnt brick in cut stone arch work including all charges	,,	200		
8	Burnt stone slabs 6″ thick dressed and fixed in position for plinth, cills and lintels ..	S.ft.	140		
9	Plastering with mortar	100 S.ft.	4,000		
10	Pointing stone wall with cement mortar ..	,,	1,300		
11	Whitewashing, 2 coats	,,	4,000		
12	Fixing brackets of angle iron with rod, complete	No.	6		
13	Teakwood panelled doors with frames and shutters 1½″ thick including all fittings such as bolts, hinges, as per specification.	S.ft.	91		
14	Teakwood windows with glazed shutters inside and panelled outside with iron bars ¾″ dia. including all fittings, complete ..	,,	42		
15	Teakwood ticket window with fittings complete as per standard design	,,	16		
16	Teakwood barricade with turned legs in front of ticket window in 3rd class Waiting Shed and fixing as per plan and specification.	,,	23		
17	Teakwood trusses 16 ft. clear span complete with iron work and fittings as per sample.	No.	1		

Sl. No.	Items of work	Unit	Quantity	Rate	Cost
				Rs. a. p.	Rs. a. p.
18	Fixing teakwood trusses supplied departmentally including cleaning and wood oiling	No.	2		
19	Handling and fixing 50 lbs. rails	R.ft.	89		
20	Wall rack with teakwood plank $1\frac{1}{4}''$ thick and brackets 2" square and 2 ft. apart including fitting, etc., complete ..	S.ft.	132		
21	Teakwood shelves with panelled shutters and two rows of planks 1" thick, complete.	S.ft.	24		
22	Teakwood wrought and put up including wood oiling, 2 coats	C.ft.	113·82		
23	Cleaning and putting up Departmental T. W. purlins	,,	15		
24	Roofing with 1st class Mangalore tiles over teakwood reepers $2''\times1''$ wood oiled 2 coats including T. W. wind ties $2''\times1\frac{1}{2}''$ fixed with $3\frac{1}{2}''$ screws chunam borders, etc., complete with R.M.C. for tiles from Yelahanka to Belagula	100 S.ft.	2,570		
25	Ridge tiles set in mortar with R.M.C. for tiles from Yelahanka to Belagula	R.ft.	54		
26	T. W. eave boards $9''\times\frac{3}{4}''$ including painting as per approved design	R.ft.	210		
27	Teakwood finials, 4 feet long	No.	2		
28	Teakwood pendents	,,	4		
29	Painting with silicate silver grey 2 coats ..	100 S.ft.	500		
30	Providing cement boards on walls with borders 2" thick all round (5'×4') ..	No.	4		
31	Flooring with granite slabs 3" to 4" thick, two line dressed over 2" concrete broken stone in mortar including cement pointing, etc., complete with R.M.C. for slabs, to Belagula station from any station on Mysore Railways	100 S.ft.	1,490		
32	Large boards with teakwood planks $\frac{3}{4}''$ thick as per approved design	S.ft.	70		
33	Fixing C.I. railing for openings of Waiting Room	No.	2		
34	Fixing C.I. gates with double shutters $7'\times4\frac{1}{2}'$ each	,,	1		
35	Preparing and fixing Indian Refreshment Stall in teakwood, as per design	S.ft.	160		
36	Cut stone pillars 7" to 8" sqr., with base and capital to suit over-all height 8'–6" ..	No.	3		
37	Earthwork and removal of rubbish, etc., and levelling ground all round the building after completion	1,000 C.ft.	10,000		
	N.B.—Items not included in this schedule will be paid for at the average Divisional rates.				

M. RAMAIYA,
Executive Engineer.

INDIAN POSTS AND TELEGRAPHS DEPARTMENTS.

Notice.

Sealed tenders are invited for the conveyance of mails by motor vehicles daily between Hassan and Arkalgud and Kerlapura for up and down journeys throughout the year on a fixed monthly subsidy for a period of three years commencing from the date to be fixed later. The form of tender and a copy of the schedule showing the number, timings and other details of the service required